

**County Line Road  
Safety and Operational Improvements  
Fact Sheet  
December 13, 2007**

<b>Project No.:</b>	D6070
<b>Description:</b>	County Line Road Safety and Operational Improvement Project.
<b>Existing Typical Section:</b>	Two 10 to 11-foot lanes divided with grassed rural on both sides and intermittent sections of curb and gutter and sidewalk.
<b>Proposed Typical Section:</b>	One 11-foot travel lane with 1-foot paved shoulder in each direction and a 10-foot shoulder with 24" curb and gutter, 18" grass strip, and 5-foot sidewalk on the south/east side and maintaining the existing rural shoulder on the north/west side.
<b>Length:</b>	4.25 miles
<b>Speed Design:</b>	35 mph
<b>Tentative Schedule:</b>	Preliminary Plans – December 2007 to March 2008 Right of Way Plans – March 2008 to April 2008 Right of Way Acquisition – May 2008 to December 2008 Final Plans – June 2008 to September 2008 Construction – Start early 2009
<b>Construction Time:</b>	12 months
<b>Approximate Construction Cost:</b>	\$6,700,000
<b>Estimated Right of Way:</b>	95 Parcels 0 Potential Commercial Displacements 0 Potential Residential Displacements
<b>Environmental:</b>	Environmental screening and permitting. A CE is not required because local funding only.
<b>Signalized Intersections:</b>	Non Anticipated